ARCLOOM / DESIGN REPORT

Six-storey courtyard Geometry QA

Concept quantities | INR | 6 floors

Building summary

Gross floor footprint including openings: 1,920 m2

Entered rates subtotal: INR 0

9 items unpriced. This subtotal is not a complete construction budget.

Quantities and entered rates

Floor slab concrete

320 m3 | Rate: Unpriced | Amount: Unpriced

1600 m2 modelled slab area 0.2 m assumed thickness; explicit floor openings deducted, other core holes not inferred.

Floor opening area

320 m2 | Rate: Unpriced | Amount: Unpriced

Union of explicit openings across floors; already deducted from slab concrete. Any entered rate is a separate opening allowance.

Wall masonry / partitions

626.11 m3 | Rate: Unpriced | Amount: Unpriced

Unique wall segments with modelled openings deducted; junction volumes approximate.

Wall finishes, both faces

5,146.08 m2 | Rate: Unpriced | Amount: Unpriced

Both faces of modelled wall segments; openings deducted, reveals excluded.

Door sets

1 each | Rate: Unpriced | Amount: Unpriced

Door objects in all floors; no doors inferred from room labels.

Window glazing

61.2 m2 | Rate: Unpriced | Amount: Unpriced

Opening width modelled glazing height; frame allowances excluded.

Room floor finishes (gross)

1,536 m2 | Rate: Unpriced | Amount: Unpriced

Sum of labelled rectangle areas; overlapping areas are not deducted.

Landscape area

64 m2 | Rate: Unpriced | Amount: Unpriced

Sum of labelled rectangle areas; overlapping areas are not deducted.

Six-storey courtyard Geometry QA

Concept quantities | INR | 6 floors

Plant fixtures

1 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Six-storey courtyard Geometry QA

Concept quantities | INR | 6 floors

Room and space schedule

Ground Courtyard

Public entrance West gallery | 6 x 16 m | 96 m2

East gallery | 6 x 16 m | 96 m2

North gallery | 8 x 4 m | 32 m2

South gallery | 8 x 4 m | 32 m2

Courtyard garden | 8 x 8 m | 64 m2

Level 1 Gallery

West gallery | 6 x 16 m | 96 m2

East gallery | 6 x 16 m | 96 m2

North gallery | 8 x 4 m | 32 m2

South gallery | 8 x 4 m | 32 m2

[Floor opening] Atrium open to below | 8 x 8 m | 64 m2

Level 2 Gallery

West gallery | 6 x 16 m | 96 m2

East gallery | 6 x 16 m | 96 m2

North gallery | 8 x 4 m | 32 m2

South gallery | 8 x 4 m | 32 m2

[Floor opening] Atrium open to below | 8 x 8 m | 64 m2

Level 3 Gallery

West gallery | 6 x 16 m | 96 m2

East gallery | 6 x 16 m | 96 m2

North gallery | 8 x 4 m | 32 m2

South gallery | 8 x 4 m | 32 m2

[Floor opening] Atrium open to below | 8 x 8 m | 64 m2

Level 4 Gallery

West gallery | 6 x 16 m | 96 m2

East gallery | 6 x 16 m | 96 m2

North gallery | 8 x 4 m | 32 m2

South gallery | 8 x 4 m | 32 m2

[Floor opening] Atrium open to below | 8 x 8 m | 64 m2

Level 5 Gallery

West gallery | 6 x 16 m | 96 m2

ARCLOOM / DESIGN REPORT

Six-storey courtyard Geometry QA

Concept quantities | INR | 6 floors

East gallery | 6 x 16 m | 96 m2

North gallery | 8 x 4 m | 32 m2

South gallery | 8 x 4 m | 32 m2

[Floor opening] Atrium open to below | 8 x 8 m | 64 m2

Design assumptions and unresolved issues

Authored six-storey fixture for courtyard rendering and quantity verification, not an AI-generated programme. Guardrails, structural edges and compliance are not modelled.

Basis and exclusions

Concept quantities, not a priced construction tender.

No foundations, reinforcement, structural sizing, MEP, earthworks, taxes or contractor allowances are inferred.

Enter local supplier or estimator rates. Blank rates remain unpriced.