ARCLOOM / DESIGN REPORT

# Access review example

Concept quantities | INR | 1 floor

## Building summary

Gross floor area: 108 m2

Entered rates subtotal: INR 0

8 items unpriced. This subtotal is not a complete construction budget.

## Quantities and entered rates

### Floor slab concrete

21.6 m3 | Rate: Unpriced | Amount: Unpriced

Gross floor footprint assumed slab thickness; core holes not deducted.

### Wall masonry / partitions

50.77 m3 | Rate: Unpriced | Amount: Unpriced

Unique wall segments with modelled openings deducted; junction volumes approximate.

### Wall finishes, both faces

414.24 m2 | Rate: Unpriced | Amount: Unpriced

Both faces of modelled wall segments; openings deducted, reveals excluded.

### Door sets

4 each | Rate: Unpriced | Amount: Unpriced

Door objects in all floors; no doors inferred from room labels.

### Window glazing

0 m2 | Rate: Unpriced | Amount: Unpriced

Opening width modelled glazing height; frame allowances excluded.

### Room floor finishes (gross)

108 m2 | Rate: Unpriced | Amount: Unpriced

Sum of labelled rectangle areas; overlapping areas are not deducted.

### Bed fixtures

2 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Shower fixtures

2 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

ARCLOOM / DESIGN REPORT

# Access review example

Concept quantities | INR | 1 floor

## Room and space schedule

### Guest accommodation

Double bedroom | 6 x 6 m | 36 m2

Rotated bedroom | 6 x 6 m | 36 m2

Bathroom A | 3 x 3 m | 9 m2

Entrance hallway | 6 x 3 m | 18 m2

Bathroom B | 3 x 3 m | 9 m2

## Basis and exclusions

Concept quantities, not a priced construction tender.

No foundations, reinforcement, structural sizing, MEP, earthworks, taxes or contractor allowances are inferred.

Enter local supplier or estimator rates. Blank rates remain unpriced.

Guest accommodation: Bathroom B has no modelled door or open passage on its boundary.