ARCLOOM / DESIGN REPORT

THE ATRIUM

Concept quantities | INR | 8 floors

Building summary

Gross floor area: 13,824 m2

Entered rates subtotal: INR 0

22 items unpriced. This subtotal is not a complete construction budget.

Quantities and entered rates

Floor slab concrete

2,764.8 m3 | Rate: Unpriced | Amount: Unpriced

Gross floor footprint assumed slab thickness; core holes not deducted.

Wall masonry / partitions

3,249.41 m3 | Rate: Unpriced | Amount: Unpriced

Unique wall segments with modelled openings deducted; junction volumes approximate.

Wall finishes, both faces

30,949.08 m2 | Rate: Unpriced | Amount: Unpriced

Both faces of modelled wall segments; openings deducted, reveals excluded.

Door sets

141 each | Rate: Unpriced | Amount: Unpriced

Door objects in all floors; no doors inferred from room labels.

Window glazing

428.4 m2 | Rate: Unpriced | Amount: Unpriced

Opening width modelled glazing height; frame allowances excluded.

Room floor finishes (gross)

13,286 m2 | Rate: Unpriced | Amount: Unpriced

Sum of labelled rectangle areas; overlapping areas are not deducted.

Landscape area

442 m2 | Rate: Unpriced | Amount: Unpriced

Sum of labelled rectangle areas; overlapping areas are not deducted.

Stair fixtures

16 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

THE ATRIUM

Concept quantities | INR | 8 floors

Lift fixtures

24 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Counter fixtures

10 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Desk fixtures

24 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Chair fixtures

91 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Sofa fixtures

13 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Table fixtures

40 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Plant fixtures

4 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Rack fixtures

19 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Kitchen fixtures

7 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Sink fixtures

41 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

THE ATRIUM

Concept quantities | INR | 8 floors

Toilet fixtures

29 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Cabinet fixtures

37 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Bed fixtures

31 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

Shower fixtures

22 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

THE ATRIUM

Concept quantities | INR | 8 floors

Room and space schedule

Ground Arrival

Guest stair A | 3 x 8 m | 24 m2

Passenger lift A | 3 x 3 m | 9 m2

Passenger lift B | 3 x 3 m | 9 m2

Guest core lobby | 3 x 4 m | 12 m2

Guest circulation | 6 x 26 m | 156 m2

Service stair B | 3 x 8 m | 24 m2

Service lift | 3 x 4 m | 12 m2

Service core lobby | 3 x 6 m | 18 m2

Staff circulation | 6 x 26 m | 156 m2

Arrival gallery | 36 x 3 m | 108 m2

Service corridor | 36 x 3 m | 108 m2

Reception and concierge | 15 x 10 m | 150 m2

Lobby lounge | 13 x 10 m | 130 m2

Retail boutique | 8 x 10 m | 80 m2

Cafe dining | 16 x 17 m | 272 m2

Cafe kitchen | 8 x 10 m | 80 m2

Guest toilets | 8 x 7 m | 56 m2

Loading and receiving | 12 x 9 m | 108 m2

Laundry and linen | 12 x 8 m | 96 m2

Staff room and lockers | 12 x 3 m | 36 m2

Security office | 8 x 3 m | 24 m2

Waste holding | 8 x 3 m | 24 m2

Building services | 8 x 3 m | 24 m2

Level 1 Convention

Guest stair A | 3 x 8 m | 24 m2

Passenger lift A | 3 x 3 m | 9 m2

Passenger lift B | 3 x 3 m | 9 m2

Guest core lobby | 3 x 4 m | 12 m2

Guest circulation | 6 x 26 m | 156 m2

Service stair B | 3 x 8 m | 24 m2

Service lift | 3 x 4 m | 12 m2

Service core lobby | 3 x 6 m | 18 m2

Staff circulation | 6 x 26 m | 156 m2

Prefunction gallery | 36 x 3 m | 108 m2

THE ATRIUM

Concept quantities | INR | 8 floors

Banquet service corridor | 36 x 3 m | 108 m2

Meeting room 1 | 10 x 10 m | 100 m2

Meeting room 2 | 10 x 10 m | 100 m2

Meeting room 3 | 10 x 10 m | 100 m2

Guest toilets | 6 x 10 m | 60 m2

Ballroom A | 12 x 17 m | 204 m2

Ballroom B | 12 x 17 m | 204 m2

Banquet kitchen | 12 x 11 m | 132 m2

Dishwash and plating | 12 x 6 m | 72 m2

Furniture store | 12 x 3 m | 36 m2

Event office | 8 x 3 m | 24 m2

Cold and dry stores | 10 x 3 m | 30 m2

AV equipment | 6 x 3 m | 18 m2

Level 2 Coworking Club

Guest stair A | 3 x 8 m | 24 m2

Passenger lift A | 3 x 3 m | 9 m2

Passenger lift B | 3 x 3 m | 9 m2

Guest core lobby | 3 x 4 m | 12 m2

Club circulation | 6 x 26 m | 156 m2

Service stair B | 3 x 8 m | 24 m2

Service lift | 3 x 4 m | 12 m2

Service core lobby | 3 x 6 m | 18 m2

Staff circulation | 6 x 26 m | 156 m2

Club gallery | 36 x 3 m | 108 m2

Service corridor | 36 x 3 m | 108 m2

Private office A | 7 x 10 m | 70 m2

Private office B | 7 x 10 m | 70 m2

Meeting room A | 8 x 10 m | 80 m2

Meeting room B | 8 x 10 m | 80 m2

Guest toilets | 6 x 10 m | 60 m2

Coworking studio | 20 x 17 m | 340 m2

Club reception and lounge | 8 x 17 m | 136 m2

Open club terrace | 8 x 17 m | 136 m2

Pantry | 12 x 3 m | 36 m2

Quiet room | 8 x 3 m | 24 m2

IT and server room | 8 x 3 m | 24 m2

THE ATRIUM

Concept quantities | INR | 8 floors

Club store | 8 x 3 m | 24 m2

Level 3 Deluxe and Family Rooms

Guest stair A | 3 x 8 m | 24 m2

Passenger lift A | 3 x 3 m | 9 m2

Passenger lift B | 3 x 3 m | 9 m2

Guest core lobby | 3 x 4 m | 12 m2

Guest circulation | 6 x 26 m | 156 m2

Service stair B | 3 x 8 m | 24 m2

Service lift | 3 x 4 m | 12 m2

Service core lobby | 3 x 6 m | 18 m2

Staff circulation | 6 x 26 m | 156 m2

Guest gallery | 36 x 3 m | 108 m2

Housekeeping corridor | 36 x 3 m | 108 m2

301 Deluxe king | 6 x 10 m | 60 m2

301 Ensuite | 3 x 5 m | 15 m2

301 Dressing | 3 x 5 m | 15 m2

302 Deluxe king | 6 x 10 m | 60 m2

302 Ensuite | 3 x 5 m | 15 m2

302 Dressing | 3 x 5 m | 15 m2

303 Deluxe twin | 6 x 10 m | 60 m2

303 Ensuite | 3 x 5 m | 15 m2

303 Dressing | 3 x 5 m | 15 m2

304 Accessible king | 6 x 10 m | 60 m2

304 Ensuite | 3 x 5 m | 15 m2

304 Dressing | 3 x 5 m | 15 m2

305 Family bedroom | 8 x 17 m | 136 m2

305 Dressing | 4 x 9 m | 36 m2

305 Ensuite | 4 x 8 m | 32 m2

306 Family bedroom | 8 x 17 m | 136 m2

306 Dressing | 4 x 9 m | 36 m2

306 Ensuite | 4 x 8 m | 32 m2

307 Junior suite | 8 x 17 m | 136 m2

307 Dressing | 4 x 9 m | 36 m2

307 Ensuite | 4 x 8 m | 32 m2

Housekeeping and linen | 18 x 3 m | 54 m2

Staff WC and services | 18 x 3 m | 54 m2

THE ATRIUM

Concept quantities | INR | 8 floors

Level 4 Business Kings and Twins

Guest stair A | 3 x 8 m | 24 m2

Passenger lift A | 3 x 3 m | 9 m2

Passenger lift B | 3 x 3 m | 9 m2

Guest core lobby | 3 x 4 m | 12 m2

Guest circulation | 6 x 26 m | 156 m2

Service stair B | 3 x 8 m | 24 m2

Service lift | 3 x 4 m | 12 m2

Service core lobby | 3 x 6 m | 18 m2

Staff circulation | 6 x 26 m | 156 m2

Guest gallery | 36 x 3 m | 108 m2

Housekeeping corridor | 36 x 3 m | 108 m2

401 Business king | 9 x 10 m | 90 m2

401 Ensuite | 3 x 5 m | 15 m2

401 Dressing | 3 x 5 m | 15 m2

402 Business twin | 9 x 10 m | 90 m2

402 Ensuite | 3 x 5 m | 15 m2

402 Dressing | 3 x 5 m | 15 m2

403 Business king | 9 x 10 m | 90 m2

403 Ensuite | 3 x 5 m | 15 m2

403 Dressing | 3 x 5 m | 15 m2

404 Executive twin | 8 x 17 m | 136 m2

404 Dressing | 4 x 9 m | 36 m2

404 Ensuite | 4 x 8 m | 32 m2

405 Executive king | 8 x 17 m | 136 m2

405 Dressing | 4 x 9 m | 36 m2

405 Ensuite | 4 x 8 m | 32 m2

406 Executive twin | 8 x 17 m | 136 m2

406 Dressing | 4 x 9 m | 36 m2

406 Ensuite | 4 x 8 m | 32 m2

Housekeeping and linen | 18 x 3 m | 54 m2

Staff WC and services | 18 x 3 m | 54 m2

Level 5 Family and Residential Suites

Guest stair A | 3 x 8 m | 24 m2

Passenger lift A | 3 x 3 m | 9 m2

Passenger lift B | 3 x 3 m | 9 m2

THE ATRIUM

Concept quantities | INR | 8 floors

Guest core lobby | 3 x 4 m | 12 m2

Guest circulation | 6 x 26 m | 156 m2

Service stair B | 3 x 8 m | 24 m2

Service lift | 3 x 4 m | 12 m2

Service core lobby | 3 x 6 m | 18 m2

Staff circulation | 6 x 26 m | 156 m2

Guest gallery | 36 x 3 m | 108 m2

Housekeeping corridor | 36 x 3 m | 108 m2

501 Family king | 9 x 10 m | 90 m2

501 Ensuite | 3 x 5 m | 15 m2

501 Dressing | 3 x 5 m | 15 m2

502 Family twin | 9 x 10 m | 90 m2

502 Ensuite | 3 x 5 m | 15 m2

502 Dressing | 3 x 5 m | 15 m2

503 Family king | 9 x 10 m | 90 m2

503 Ensuite | 3 x 5 m | 15 m2

503 Dressing | 3 x 5 m | 15 m2

504 Suite living and dining | 18 x 8 m | 144 m2

504 King bedroom | 10 x 9 m | 90 m2

504 Dressing | 8 x 4 m | 32 m2

504 Ensuite | 8 x 5 m | 40 m2

505 Suite living and dining | 18 x 8 m | 144 m2

505 Twin bedroom | 10 x 9 m | 90 m2

505 Dressing | 8 x 4 m | 32 m2

505 Ensuite | 8 x 5 m | 40 m2

Housekeeping and linen | 18 x 3 m | 54 m2

Staff WC and services | 18 x 3 m | 54 m2

Level 6 Premium Suites

Guest stair A | 3 x 8 m | 24 m2

Passenger lift A | 3 x 3 m | 9 m2

Passenger lift B | 3 x 3 m | 9 m2

Guest core lobby | 3 x 4 m | 12 m2

Guest circulation | 6 x 26 m | 156 m2

Service stair B | 3 x 8 m | 24 m2

Service lift | 3 x 4 m | 12 m2

Service core lobby | 3 x 6 m | 18 m2

THE ATRIUM

Concept quantities | INR | 8 floors

Staff circulation | 6 x 26 m | 156 m2

Executive gallery | 36 x 3 m | 108 m2

Housekeeping corridor | 36 x 3 m | 108 m2

Executive lounge | 24 x 10 m | 240 m2

Lounge pantry | 6 x 10 m | 60 m2

Guest toilets | 6 x 10 m | 60 m2

601 Premium living room | 18 x 8 m | 144 m2

601 King bedroom | 10 x 9 m | 90 m2

601 Dressing room | 8 x 4 m | 32 m2

601 Ensuite | 8 x 5 m | 40 m2

602 Premium living room | 18 x 8 m | 144 m2

602 King bedroom | 10 x 9 m | 90 m2

602 Dressing room | 8 x 4 m | 32 m2

602 Ensuite | 8 x 5 m | 40 m2

Housekeeping and linen | 18 x 3 m | 54 m2

Staff WC and services | 18 x 3 m | 54 m2

Level 7 Rooftop Dining and Wellness

Guest stair A | 3 x 8 m | 24 m2

Passenger lift A | 3 x 3 m | 9 m2

Passenger lift B | 3 x 3 m | 9 m2

Guest core lobby | 3 x 4 m | 12 m2

Guest circulation | 6 x 26 m | 156 m2

Service stair B | 3 x 8 m | 24 m2

Service lift | 3 x 4 m | 12 m2

Service core lobby | 3 x 6 m | 18 m2

Staff circulation | 6 x 26 m | 156 m2

Rooftop arrival gallery | 36 x 3 m | 108 m2

Service corridor | 36 x 3 m | 108 m2

Rooftop restaurant | 20 x 10 m | 200 m2

Sky bar | 10 x 10 m | 100 m2

Guest toilets | 6 x 10 m | 60 m2

Landscaped roof terrace | 18 x 17 m | 306 m2

Gym | 10 x 11 m | 110 m2

Changing room A | 5 x 6 m | 30 m2

Changing room B | 5 x 6 m | 30 m2

Restaurant kitchen | 8 x 11 m | 88 m2

THE ATRIUM

Concept quantities | INR | 8 floors

Wash and cold store | 8 x 6 m | 48 m2

Screened plant room | 18 x 3 m | 54 m2

Roof maintenance store | 8 x 3 m | 24 m2

Staff facilities | 10 x 3 m | 30 m2

Design assumptions and unresolved issues

Full replacement review proposal preserving project ID; building schema enables eight separately editable floors, doors, glazing and fixtures.

The concept contains 211 non-overlapping space rectangles across eight floors. Furnishings and openings are separate editable collections.

North is assumed at the top. Public arrival is from the west; ground-level loading enters from the east. Site roads, setbacks and external vehicle manoeuvring are outside this footprint.

Two stairs, two passenger lifts and one service lift align on all eight floors. West circulation serves guests; east circulation and the southern service corridor serve staff. Controlled crossover doors connect the routes.

Passenger lift doorways open west into the guest stair/core zone, which connects through the lobby and west circulation. Detailed lift lobbies and stair enclosures require professional development.

South-facing hotel accommodation is buffered by the service band; its daylight concept relies on borrowed light from glazed side circulation. Direct exterior glazing to every bedroom would require revising the perimeter circulation strategy.

Proposed hotel mix: seven keys on level 3, six on level 4, five on level 5 and two premium suites on level 6. A higher room count has not been assumed.

Ballroom A and B have an editable large connecting opening representing a retractable acoustic divider; partition storage, event capacity and AV layouts remain conceptual.

Level 2 has a genuine open terrace; level 7 has a separately reserved landscaped terrace. Waterproofing, drainage, guards and wind protection remain unresolved.

THE ATRIUM is treated as the hotel name; no multi-floor void is assumed because no atrium size or location was provided.

Room rectangles describe planning extents with 0.18 m internal walls. The intended 0.28 m external envelope requires a separate detailed envelope model.

All floor heights are assumed at 4 m. Convention clear heights, rooftop plant loads, structural transfers, wet-service risers, acoustic separation and kitchen exhaust routes require coordination.

Fixtures illustrate a low-density furnished concept, not a final seating, occupancy or equipment schedule. Toilet suites and staff WC/service rooms require further stall and privacy subdivision.

Basis and exclusions

Concept quantities, not a priced construction tender.

THE ATRIUM

Concept quantities | INR | 8 floors

No foundations, reinforcement, structural sizing, MEP, earthworks, taxes or contractor allowances are inferred.

Enter local supplier or estimator rates. Blank rates remain unpriced.