KOSAL STUDIO / DESIGN REPORT

# Kosal Commons  Bank / Cafe / IT

Concept quantities | INR | 3 floors

## Building summary

Gross floor area: 2,160 m2

Entered rates subtotal: INR 43,200

22 items unpriced. This subtotal is not a complete construction budget.

## Quantities and entered rates

### Floor slab concrete

432 m3 | Rate: INR 100 | Amount: INR 43,200

Gross floor footprint assumed slab thickness; core holes not deducted.

### Wall masonry / partitions

681.83 m3 | Rate: Unpriced | Amount: Unpriced

Unique wall segments with modelled openings deducted; junction volumes approximate.

### Wall finishes, both faces

6,437.54 m2 | Rate: Unpriced | Amount: Unpriced

Both faces of modelled wall segments; openings deducted, reveals excluded.

### Door sets

63 each | Rate: Unpriced | Amount: Unpriced

Door objects in all floors; no doors inferred from room labels.

### Window glazing

179.52 m2 | Rate: Unpriced | Amount: Unpriced

Opening width modelled glazing height; frame allowances excluded.

### Room floor finishes (gross)

2,136 m2 | Rate: Unpriced | Amount: Unpriced

Sum of labelled rectangle areas; overlapping areas are not deducted.

### Landscape area

24 m2 | Rate: Unpriced | Amount: Unpriced

Sum of labelled rectangle areas; overlapping areas are not deducted.

### Stair fixtures

6 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

KOSAL STUDIO / DESIGN REPORT

# Kosal Commons  Bank / Cafe / IT

Concept quantities | INR | 3 floors

### Lift fixtures

3 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Toilet fixtures

12 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Sink fixtures

14 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Safe fixtures

1 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Cabinet fixtures

5 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Desk fixtures

36 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Chair fixtures

146 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Rack fixtures

10 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Sofa fixtures

5 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Kitchen fixtures

4 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

KOSAL STUDIO / DESIGN REPORT

# Kosal Commons  Bank / Cafe / IT

Concept quantities | INR | 3 floors

### Table fixtures

17 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Teller fixtures

4 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Counter fixtures

4 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Atm fixtures

2 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

### Plant fixtures

9 each | Rate: Unpriced | Amount: Unpriced

Count of editable fixture objects across all floors.

KOSAL STUDIO / DESIGN REPORT

# Kosal Commons  Bank / Cafe / IT

Concept quantities | INR | 3 floors

## Room and space schedule

### Ground floor  Bank

Stair A protected core | 4 x 6 m | 24 m2

Lift lobby | 4 x 3 m | 12 m2

Accessible WC | 4 x 4 m | 16 m2

Staff WC / services | 4 x 4 m | 16 m2

Tenant entry lobby | 4 x 7 m | 28 m2

West circulation | 2 x 24 m | 48 m2

Main circulation | 20 x 4 m | 80 m2

Electrical / risers | 4 x 4 m | 16 m2

Washrooms | 4 x 6 m | 24 m2

East circulation | 4 x 8 m | 32 m2

Stair B protected core | 4 x 6 m | 24 m2

Secure vault | 6 x 6 m | 36 m2

Cash processing | 6 x 6 m | 36 m2

IT / security server | 4 x 6 m | 24 m2

Branch manager | 4 x 6 m | 24 m2

Bank operations | 10 x 4 m | 40 m2

Staff lounge | 6 x 4 m | 24 m2

Security / control | 4 x 4 m | 16 m2

Teller hall | 12 x 4 m | 48 m2

Consultation 01 | 4 x 4 m | 16 m2

Consultation 02 | 4 x 4 m | 16 m2

Customer waiting | 10 x 6 m | 60 m2

Public entrance / reception | 6 x 6 m | 36 m2

ATM vestibule | 4 x 6 m | 24 m2

### Level 1  Cafe

Stair A protected core | 4 x 6 m | 24 m2

Lift lobby | 4 x 3 m | 12 m2

Accessible WC | 4 x 4 m | 16 m2

Staff WC / services | 4 x 4 m | 16 m2

Tenant entry lobby | 4 x 7 m | 28 m2

West circulation | 2 x 24 m | 48 m2

Main circulation | 20 x 4 m | 80 m2

Electrical / risers | 4 x 4 m | 16 m2

Washrooms | 4 x 6 m | 24 m2

KOSAL STUDIO / DESIGN REPORT

# Kosal Commons  Bank / Cafe / IT

Concept quantities | INR | 3 floors

East circulation | 4 x 8 m | 32 m2

Stair B protected core | 4 x 6 m | 24 m2

Production kitchen | 12 x 6 m | 72 m2

Dishwash / wet area | 4 x 6 m | 24 m2

Dry & cold storage | 4 x 6 m | 24 m2

Pastry / preparation | 6 x 4 m | 24 m2

Coffee bar / pickup | 8 x 4 m | 32 m2

Staff changing | 6 x 4 m | 24 m2

Main dining 40 seats | 14 x 10 m | 140 m2

Lounge / private dining | 6 x 6 m | 36 m2

Garden terrace | 6 x 4 m | 24 m2

### Level 2  IT company

Stair A protected core | 4 x 6 m | 24 m2

Lift lobby | 4 x 3 m | 12 m2

Accessible WC | 4 x 4 m | 16 m2

Staff WC / services | 4 x 4 m | 16 m2

Tenant entry lobby | 4 x 7 m | 28 m2

West circulation | 2 x 24 m | 48 m2

Main circulation | 20 x 4 m | 80 m2

Electrical / risers | 4 x 4 m | 16 m2

Washrooms | 4 x 6 m | 24 m2

East circulation | 4 x 8 m | 32 m2

Stair B protected core | 4 x 6 m | 24 m2

Meeting room A | 4 x 6 m | 24 m2

Meeting room B | 4 x 6 m | 24 m2

Director / management | 6 x 6 m | 36 m2

Server / network | 6 x 6 m | 36 m2

Project / training room | 10 x 4 m | 40 m2

Pantry / breakout | 10 x 4 m | 40 m2

Open office 24 workstations | 14 x 10 m | 140 m2

Collaboration lounge | 6 x 4 m | 24 m2

Focus booth A | 3 x 3 m | 9 m2

Focus booth B | 3 x 3 m | 9 m2

Print / library | 6 x 3 m | 18 m2

## Basis and exclusions

Concept quantities, not a priced construction tender.

KOSAL STUDIO / DESIGN REPORT

# Kosal Commons  Bank / Cafe / IT

Concept quantities | INR | 3 floors

No foundations, reinforcement, structural sizing, MEP, earthworks, taxes or contractor allowances are inferred.

Enter local supplier or estimator rates. Blank rates remain unpriced.